INTERNATIONAL STANDARD

ISO 14617-8

First edition 2002-09-01

Graphical symbols for diagrams —

Part 8: Valves and dampers

Symboles graphiques pour schémas — Partie 8: Appareils de robinetterie et registres



Reference number ISO 14617-8:2002(E)

PDF disclaimer

This PDF file may contain embedded typefaces. In accordance with Adobe's licensing policy, this file may be printed or viewed but shall not be edited unless the typefaces which are embedded are licensed to and installed on the computer performing the editing. In downloading this file, parties accept therein the responsibility of not infringing Adobe's licensing policy. The ISO Central Secretariat accepts no liability in this

Adobe is a trademark of Adobe Systems Incorporated.

Details of the software products used to create this PDF file can be found in the General Info relative to the file; the PDF-creation parameters were optimized for printing. Every care has been taken to ensure that the file is suitable for use by ISO member bodies. In the unlikely event that a problem relating to it is found, please inform the Central Secretariat at the address given below.

© ISO 2002

All rights reserved. Unless otherwise specified, no part of this publication may be reproduced or utilized in any form or by any means, electronic or mechanical, including photocopying and microfilm, without permission in writing from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office Case postale 56 • CH-1211 Geneva 20 Tel. + 41 22 749 01 11 Fax + 41 22 749 09 47 E-mail copyright@iso.ch Web www.iso.ch

Printed in Switzerland

Cont	Contents		
Forew	ord	iv	
Introd	uction	v	
1 5	Scope	1	
2	Normative references	1	
3	Terms and definitions	1	
4	General-purpose valves	3	
5	Dampers	9	
6	Valves for fluid power systems	10	
7	Hygienic valves	20	
8	Valves with special functions		
Biblio	graphy	23	

Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

International Standards are drafted in accordance with the rules given in the ISO/IEC Directives, Part 3.

The main task of technical committees is to prepare International Standards. Draft International Standards adopted by the technical committees are circulated to the member bodies for voting. Publication as an International Standard requires approval by at least 75 % of the member bodies casting a vote.

Attention is drawn to the possibility that some of the elements of this part of ISO 14617 may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights.

ISO 14617-8 was prepared by Technical Committee ISO/TC 10, *Technical product documentation*, Subcommittee SC 10, *Process plant documentation and tpd-symbols*.

ISO 14617 consists of the following parts, under the general title Graphical symbols for diagrams:

- Part 1: General information and indexes
- Part 2: Symbols having general application
- Part 3: Connections and related devices
- Part 4: Actuators and related devices
- Part 5: Measurement and control devices
- Part 6: Measurement and control functions
- Part 7: Basic mechanical components
- Part 8: Valves and dampers
- Part 9: Pumps, compressors and fans
- Part 10: Fluid power converters
- Part 11: Devices for heat transfer and heat engines
- Part 12: Devices for separating, purification and mixing
- Part 15: Installation diagrams and network maps

Other parts are under preparation.

Introduction

The purpose of ISO 14617 in its final form is the creation of a library of harmonized graphical symbols for diagrams used in technical applications. This work has been, and will be, performed in close cooperation between ISO and IEC. The ultimate result is intended to be published as a standard common to ISO and IEC, which their technical committees responsible for specific application fields can use in preparing International Standards and manuals.

Graphical symbols for diagrams —

Part 8:

Valves and dampers

1 Scope

This part of ISO 14617 specifies graphical symbols for valves and dampers in diagrams, including symbols for general-purpose valves, those used in fluid power systems and hygienic valves used in the food and pharmaceutical industries.

For the fundamental rules of creation and application of graphical symbols in diagrams, see ISO 81714-1.

For an overview of ISO 14617, information on the creation and use of registration numbers for identifying graphical symbols used in diagrams, rules for the presentation and application of these symbols, and examples of their use and application, see ISO 14617-1.

2 Normative references

The following normative documents contain provisions which, through reference in this text, constitute provisions of this part of ISO 14617. For dated references, subsequent amendments to, or revisions of, any of these publications do not apply. However, parties to agreements based on this part of ISO 14617 are encouraged to investigate the possibility of applying the most recent editions of the normative documents indicated below. For undated references, the latest edition of the normative document referred to applies. Members of ISO and IEC maintain registers of currently valid International Standards.

ISO 14617-1:2002, Graphical symbols for diagrams — Part 1: General information and indexes

ISO 14617-2:2002, Graphical symbols for diagrams — Part 2: Symbols having general application

ISO 14617-4:2002, Graphical symbols for diagrams — Part 4: Actuators and related devices

ISO 81714-1:1999, Design of graphical symbols for use in the technical documentation of products — Part 1: Basic rules

3 Terms and definitions

For the purposes of this part of ISO 14617, the following terms and definitions apply.

NOTE The list has been restricted to terms whose meaning is not obvious and which have not been defined elsewhere in an International Standard, or which have been defined in various ways in different standards. In preparing these definitions, ISO and IEC standards on terminology have been consulted; see the references in parentheses. However, most of the definitions in those standards were prepared by different technical committees within a restricted scope. This means that many terms so defined have to be given more general or neutral definitions when applied in the context of graphical symbols.

3.1

safety valve

valve which automatically, without the assistance of any energy other than that of the fluid concerned, discharges a certified quantity of the fluid so as to prevent a predetermined safe pressure being exceeded, and which is designed to reclose and prevent the further flow of fluid after normal pressure conditions of service have been restored

[ISO 4126-1]

3.2

vacuum valve

valve which automatically and without the assistance of any energy other than that of the gas concerned, admits gas to a pipeline or tank in order to prevent a predetermined safe underpressure being exceeded

3.3

control valve

power-operated valve in an industrial-process control system for changing the flow rate of the process fluid

[IEC 60050-351]

3.4

restrictor

device which restricts the flow of a fluid thereby creating a pressure drop

[ISO 5598]

3.5

restrictor valve

valve in which the inlet and outlet ports are interconnected through a restricted passageway

NOTE In a fixed restrictor valve, the cross-sectional area cannot be altered; in an adjustable restrictor valve, the cross-sectional area can be adjusted.

3.6

release valve

valve through which non-desired air or steam in a pipe system may be released

3.7

pressure-reducing valve

pressure regulator

valve in which, with varying inlet pressure or outlet flow, the outlet pressure remains substantially constant, but in which the inlet pressure remains higher than the selected outlet pressure

3.8

pressure-relief valve

valve which limits maximum pressure by exhausting fluid when the required pressure is reached

3.9

exhaust valve

valve in which the outlet is automatically opened to exhaust when the air pressure falls at the inlet

4 General-purpose valves

4.1 Symbols of a basic nature

NOTE For general application rules, see R2101 (4.2.1).

4.1.1	2101	 Two-way valve
		See R2102 (4.2.2).
4.1.2	2102	 Angled two-way valve
		See R2103 (4.2.3).
4.1.3	2103	 Three-way valve
4.1.4	2104	 Four-way valve

4.2 Application rules for the symbols in 4.1

4.2.1	R2101	Symbols for actuators and devices for delaying, automatic return, detaining, latching and blocking shall be chosen from ISO 14617-4.	
		The imaginary direction of movement of the link between the symbol for a valve and that of the actuator or actuating function shall be	
		towards the valve: valve closing, and	
		— from the valve: valve opening, independent of construction.	
4.2.2	R2102	The symbol may be used as a symbol for a two-way valve in general or, in those installation diagrams where it is necessary to indicate whether a valve is straight or angled, as a symbol for a straight valve.	
4.2.3	R2103	The symbol shall be used only when it is necessary to indicate the angled construction, for example, in certain installation diagrams.	

4.3 Symbols giving supplementary information

4.3.1 Functions

4.3.1.1	2111		Non-return function; check function
		V 3	Flow from left to right possible.
4.3.1.2	2112	>	Safety function
		h h	Inlet or internal side to the left.

4.3.2 Construction

NOTE For the use of the symbols, see R2121 (4.4.3).

4.3.2.1	2121		Globe type
4.3.2.2	2122	[\infty]	Ball type
4.3.2.3	2123	[XIX]	Plug type
4.3.2.4	2124		Gate type
4.3.2.5	2125	X	Needle type
4.3.2.6	2126		Disc or butterfly type
4.3.2.7	2127		Piston type; plunger type

4.3.2.8	2128	X	Diaphragm type
4.3.2.9	2129	[\X]	Hose type
4.3.2.10	2130	>	Reduced bore
4.3.2.11	2131		Jacket

4.4 Application rules for the symbols in 4.3

4.4.1	R201	The symbol should cross the centre of the symbol to which it is added. For examples, see X201 (2-5.5.1) to X206 (2-5.5.6), X2131 (4.5.4.1) and X2141 (4.5.5.1).	
		If the symbol consists of an outline in the form of a square, rectangle or circle and a symbol inside indicating the function, another location could be more appropriate. For an example, see X207 (2-5.5.7).	
4.4.2	R115	The asterisk shall be replaced with the letter symbol for the quantity or else shall be omitted. For examples, see X2121 (4.5.3.1) to X2125 (4.5.3.5).	
4.4.3	R2121	The symbols shall be used only when it is necessary to show the construction.	

4.5 Application examples

4.5.1 Shut-off valves

4.5.1.1	X2101	403, 654, 725, 2101	Two-way valve with diaphragm actuator, opening when actuated and returning automatically to closed position at cessation of actuation
4.5.1.2	X2102	403, 725, 2103	Three-way valve with diaphragm actuator
4.5.1.3	X2103	403, 2101, IEC	Two-way valve with solenoid actuator

4.5.1.4	X2104	M	Two-way valve with electric motor actuator
		403, 2101, IEC	
4.5.1.5	X2105	M	Four-way valve with actuating device of electric-motor type
		404, 741, 2104, IEC	
4.5.1.6	X2106	——————————————————————————————————————	Globe-type two-way valve with quick-release coupling, for example, for fire hydrant
		403, 405, 565, 681, 2101, 2121	
4.5.1.7	X2107		Ball-type three-way valve with double-acting fluid cylinder actuator
		403, 2103, 2113, 2442	

4.5.2 Non-return valves and check valves

4.5.2.1	X2111		Weight-loaded non-return valve
		403, 2001, 2101, 2111	
4.5.2.2	X2112		Combined non-return valve and manually actuated stop valve
		403, 681, 2101, 2111	
4.5.2.3	X2113	-	Globe-type non-return valve; lift-type non-return valve
		2101, 2111, 2121	
4.5.2.4	X2114	→ >>	Swing-type non-return valve
		2101, 2111, 2126	

4.5.2.5	X2115	3	Spring-loaded ball-type non-return valve
		403, 2002, 2101, 2122	

4.5.3 Valves with safety function

4.5.3.1	X2121	171, 242, 403, 2101, 2112	Safety valve which opens when pressure p higher than set value
4.5.3.2	X2122	▼ <i>q</i> >	Pipe break valve which closes when flow rate q is higher than set value
4.5.3.3	X2123	171, 242, 403, 2101, 2112 (M) R θ > 125 °C 171, 242, 403, 681, 741, 2002, 2101, 2112, IEC	Quick-acting valve which closes by spring actuator when temperature θ higher than 125 °C, with manual reset The spring is charged by an electric motor.
4.5.3.4	X2124	\$\rho > \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Globe type spring-loaded safety valve operating when pressure \boldsymbol{p} higher than set value
4.5.3.5	X2125	\$ p <	Angled, globe-type, spring-loaded vacuum valve operating when pressure p lower than set value
		172, 403, 2002, 2102, 2112, 2121	

4.5.4 Control valves

4.5.4.1	X2131		Control valve with actuating device of electric motor type
		201, 403, 741, 2101, IEC	

4.5.4.2	X2132		Self-operating back-pressure control valve NOTE Flow from left to right is assumed.
		201, 403, 405, 725, 2101	
4.5.4.3	X2133		Self-operating pressure reducing control valve NOTE Flow from left to right is assumed.
		201, 403, 405, 725, 2101	
4.5.4.4	X2134		Float-operated control valve
		201, 403, 715, 2101	
4.5.4.5	X2135		Spring-loaded globe-type relief valve
		201, 403, 2002, 2101, 2121	
4.5.4.6	X2136		Diaphragm-operated de-superheater control valve
		201, 301, 403, 725, 2037, 2101	
4.5.4.7	X2137		Manually operated needle-type control valve
		201, 403, 681, 2101, 2125	
4.5.4.8	X2138		Ball-type control valve, operated by diaphragm actuator or manual actuator
		201, 403, 501, 681, 725, 2101, 2122	

4.5.5 Other valves

4.5.5.1	X2141		Restrictor valve
		203, 2101	

5 Dampers

5.1 Symbols of a basic nature

5.1.1	2151	\alpha\	Two- or three-way damper
			See R2101 (4.2.1).

5.2 Application rules for the symbols in 5.1

See R2101 (4.2.1).

5.3 Symbols giving supplementary information

5.3.1	2111	\u00e4	Non-return function; check function
		173/	Flow from left to right possible.
5.3.2	2112	suti	Safety function
			Inlet is to the left.
5.3.3	201	F. 7	Adjustability
			See R201 (4.4.1).
5.3.4	203	5.7	Pre-set adjustability
			See R201 (4.4.1).

5.4 Application rules for the symbols in 5.3

See 4.4.

5.5 Application examples

5.5.1	X2151	No.	Multi-leaf damper
		2151	
5.5.2	X2152		Three-way damper with diaphragm actuator
		403, 725, 2151	

---,,-,----,,-,,-,-,-,-

5.5.3	X2153		Control damper with double-acting fluid cylinder
		201, 403, 724, 2151	

Valves for fluid power systems

6.1 Symbols of a basic nature

6.1.1	2161	*	Valve
			See R2161 (6.2.1) and R2162 (6.2.2).
6.1.2	2162	>	Seat of a non-return valve
6.1.3	2163	0	Moving part of a non-return valve

6.2 Application rules for the symbols in 6.1

6.2.1	R2161	Symbols for actuators and devices for delaying, automatic return, detaining, latching and blocking shall be chosen from ISO 14617-4.
6.2.2	R2162	The symbol shall be divided into a number of equal rectangles, one for each distinctive valve position. In each rectangle, the asterisk shall be replaced with symbols for the flow paths. However, for certain valves, a simplified representation with only one rectangle may be used. See symbol 2175 (6.3.5) and R2172 (6.4.2).

6.3 Symbols giving supplementary information

6.3.1	2171		Open flow path See R2171 (6.4.1).
6.3.2	2172		Closed flow path
6.3.3	2173		Closed flow path of a leak-free valve
6.3.4	2174	Δ	Flow to open air
6.3.5	2175		Infinite number of intermediate positions of a valve See R2172 (6.4.2).

6.3.6	2176	[Transitory position
			See R2173 (6.4.3).
6.3.7	2177	<u>[</u>	Affected area
		<u> </u>	See R2174 (6.4.4).

6.4 Application rules for the symbols in 6.3


6.4.1	R2171	When applicable, the symbol shall be supplemented with an indication of the actual flow direction. See the application examples in 6.5.	
6.4.2	R2172	For a valve with two distinct positions and an infinite number of intermediate positions a simplified representation is permitted implying that the symbol is omitted and only one rectangle drawn. For an example, see X2192 (6.5.2.2).	
6.4.3	R2173	The symbol for a transitory position shall be shown only when the flow paths in this position are necessary for the function of the circuit.	
6.4.4	R2174	The symbol for the affected area shall be used when it is necessary to show that two or more fluid circuits affect a valve on different areas. The width of the symbols shall correspond approximately to the different areas. For an example, see X2165 (6.5.1.5). Instead, the different areas may be indicated by symbols having the same width supplemented with numerical values.	

6.5 Application examples

6.5.1 Directional control valves

6.5.1.1	X2161		Manually operated directional control valve with spring return to resting position
		242, 402, 681, 2002, 2161, 2171, 2172	
6.5.1.2	X2162		Direct, pneumatically operated directional control valve with spring return to resting position
		242, 244, 2002, 2161, 2171	
6.5.1.3	X2163		Lever-operated directional control valve with three positions and spring return to resting position (mid-position)
		242, 402, 688, 2002, 2161, 2171, 2172	

6.5.1.4	X2164		Direct, hydraulically operated directional
			control valve
		242, 243, 2161, 2171	
6.5.1.5	X2165		Direct, hydraulically operated directional control valve
			Different affecting areas are indicated.
		242, 243, 2161, 2171, 2177	
6.5.1.6	X2166		Manually or electrically operated directional control valve with spring
			return
		242, 402, 681, 2002, 2161, 2171, IEC	
6.5.1.7	X2167		Electropneumatically operated directional control valve with spring return
		242, 718, 2002, 2161, 2171, IEC	
6.5.1.8	X2168		Electrohydraulically or manually operated directional control valve with spring
			return to resting position (mid-position)
		242, 402, 681, 717, 2002, 2161, 2171, 2172, IEC	
6.5.1.9	X2169		Lever-operated directional control valve, detained in all three positions
		242, 402, 656, 657, 688, 2161, 2171, 2172	
6.5.1.10	X2170	, <u>+ </u>	Manually operated directional control valve, detained in both positions with
			restricted access to actuator
		242, 402, 656, 657, 681, 692, 2161, 2171, 2172	



6.5.1.14	X2173	242, 402, 405, 422, 501, 681, 2002, 2061, 2161, 2171, 2172, IEC	Directional control valve with pilot valve: main valve having three positions, actuated by internal pilot pressure, with spring return to mid-position controlled by release of pilot pressure; pilot valve with three positions, actuated electrically or manually, with spring return to mid-position Detailed and simplified forms shown.
6.5.1.15	X2175	201, 242, 2002, 2161, 2171, 2172, 2175, IEC	Directional servo-control valve with positive overlapping in mid-position, operated by double-acting solenoid, spring return to mid-position
6.5.1.16	X2176	201, 242, 501, 2002, 2161, 2171, 2175, IEC	Directional servo-control valve with negative overlapping in mid-position, operated by two counter-acting solenoids, spring return to mid-position

6.5.1.17	X2177 X2178	242, 2002, 2031, 2161, 2171, 2172, IEC 242, 2002, 2161, 2171, 2172, IEC	Electrically operated directional control valve Detailed and simplified forms shown. In the detailed form, the transitory positions shown.
6.5.1.20	X2179 X2180	242, 422, 2161, 2171, 2172 501, 2161, 2162, 2163, 2171	Directional control valve with three ports and two positions EXAMPLE Shuttle valve with OR-function. The inlet port connected to the higher pressure is automatically connected to the outlet port while the other inlet port is closed. Detailed and simplified forms shown.
6.5.1.22	X2181 X2182	242, 246, 405, 422, 501, 561, 2161, 2171, 2172, 2173	Directional control valve with three ports and three positions EXAMPLE Shuttle valve with AND-function. The outlet port is only under pressure if both inlet ports are under pressure. Detailed and simplified forms shown.
6.5.1.23	X2183	242, 422, 2002, 2031, 2161, 2171, 2172, 2173	Directional leak-free control valve with two ports and two positions EXAMPLE Pipe break valve.

6.5.2 Pressure control valves

6.5.2.1	X2191		Single-stage pressure-relief valve
			Detailed and simplified forms shown.
		201, 242, 422, 2002, 2161, 2171, 2172, 2175	
6.5.2.2	X2192		
		201, 242, 422, 2002, 2161, 2171	
6.5.2.3	X2193		Single-stage pressure-relief valve with external drain, for use, for example, as sequence valve
		201, 242, 405, 422, 2002, 2061, 2161, 2171	
6.5.2.4	X2194		Two-stage pressure-relief valve with provision for remote control Detailed and simplified forms shown.
		201, 242, 405, 422, 501, 503, 2002, 2031, 2061, 2161, 2171	
6.5.2.5	X2195		
		201, 242, 405, 422, 501, 503, 717, 2002, 2031, 2061, 2161, 2171	

6.5.2.6	X2196		Electrohydraulically operated, two-stage pressure-relief valve
			Detailed and simplified forms shown.
		201, 242, 405, 422, 501, 717, 2002, 2061, 2161, 2171, 2172, IEC	
6.5.2.7	X2197		
		201, 242, 405, 422, 717, 2002, 2061, 2161, 2171, IEC	
6.5.2.8	X2198	r\	Pressure-reducing valve
			Detailed and simplified forms shown.
		201, 242, 422, 2002, 2161, 2171, 2172, 2175	
6.5.2.9	X2199		
		201, 242, 422, 2002, 2161, 2171	
6.5.2.10	X2200		Single-stage pressure-reducing valve
		201, 242, 405, 422, 2002, 2061, 2161, 2171	
6.5.2.11	X2201		Two-stage pressure-reducing valve
		201, 242, 405, 422, 717, 2002, 2061, 2161, 2171	

6.5.3 Flow control valves

6.5.3.1	X2211	ı	Adjustable restrictor (valve)
***************************************			Detailed and simplified forms shown.
		242, 402, 685, 2161, 2171, 2172, 2175	
6.5.3.2	X2212)(**	
		201, 2031, 2171	
6.5.3.3	X2213		Adjustable restrictor (valve) with adjustable flow in one direction and restricted flow in other direction
		201, 405, 501, 2031, 2162, 2163, 2171	
6.5.3.4	X2214	201, 242, 405, 422, 501, 2002, 2031, 2161, 2171	Flow control valve, pressure compensated Detailed and simplified forms shown.
6.5.3.5	X2215) (* q <u>p</u>	
		128, 201, 2031, 2171	

6.5.3.6	X2216	128, 201, 242, 405, 422, 501, 2002, 2031, 2161, 2171	Flow control valve, pressure and temperature compensated Detailed and simplified forms shown.
6.5.3.7	X2217	$q p, \theta$ 128, 201, 2031, 2171	
6.5.3.8	X2218	201, 242, 405, 422, 501, 2002, 2031, 2061, 2161, 2171	Flow control valve, pressure compensated, with overflow to reservoir Detailed and simplified forms shown.
6.5.3.9	X2219	128, 201, 405, 501, 2031, 2061, 2171	
6.5.3.10	X2220	128, 405, 501, 2031, 2171	Flow divider, pressure compensated The flow is divided into two flows in a fixed ratio.

6.5.4 Non-return/check valves

6.5.4.1	X2231	2002, 2162, 2163, 2171	Spring-loaded non-return valve
6.5.4.2	X2232	2161, 2162, 2163, 2171	Pilot-operated non-return valve, closed by pilot pressure
6.5.4.3	X2233	2002, 2161, 2162, 2163, 2171	Pilot-operated non-return valve, opened by pilot pressure against return spring EXAMPLE Exhaust valve.
6.5.4.4	X2234	405, 422, 501, 2002, 2161, 2162, 2163, 2171	Pilot-controlled double non-return valve

Hygienic valves

Symbols of a basic nature

The symbols of 6.1 shall be used.

Application rules for the symbols in 7.1

The application rules of 6.2 shall be used.

7.3 Symbols giving supplementary information

The symbols of 6.3 shall be used.

7.4 Application rules for the symbols in 7.3

The symbols and application rules of 6.4 shall be used.

7.5 Application examples

7.5.1	X2241	242, 2161, 2171, 2172, IEC	Hygienic valve; flow A \Rightarrow B when valve is actuated
7.5.2	X2242	A B B 242, 2161, 2171, 2172, IEC	Hygienic valve; flow A \Rightarrow B when valve in at-rest position
7.5.3	X2243	242, 501, 2161, 2171, 2172, IEC	Hygienic valve; flow B \Rightarrow C when valve is in at-rest position; flow A \Rightarrow B and A \Rightarrow C when valve is actuated
7.5.4	X2244	242, 501, 2161, 2171, 2172, IEC	Hygienic valve; flow A \Rightarrow B and A \Rightarrow C when valve is in at-rest position; flow B \Rightarrow C when valve is actuated

8 Valves with special functions

8.1 Symbol of a basic nature

8.1.1	2181	1	Self-operating release valve
			EXAMPLES Steam trap, vent.
		'	

8.2 Application rule for the symbol in 8.1

None.

8.3 Symbol giving supplementary information

None.

8.4 Application rule for the symbol in 8.3

None.

8.5 Application example


None.

Bibliography

- [1] ISO 4126-1:—1), Safety devices for protection against excessive pressure Part 1: Safety valves
- [2] ISO 5598:1985, Fluid power systems and components Vocabulary
- [3] IEC 60050-351, International Electrotechnical Vocabulary Part 351: Automatic control

1,000

¹⁾ To be published. (Revision of ISO 4126-1:1991.)



ICS 01.080.30

Price based on 23 pages

© ISO 2002 - All rights reserved

@ 10.0 0000 All dalete accessor